



TWO SCHOOL ADDITIONS COMPLETED IN ONE SUMMER

Hopkins Elementary School & Elmwood Elementary School

Triumph Modular installed modular additions on two different elementary schools in Hopkinton, MA. The new additions needed to match the look of the existing school buildings. The key reasons that modular was picked for this project were cost certainty, limiting disruption at the site, and the ability to meet an accelerated schedule.

MEASUREMENTS & STATISTICS

- Hopkins School - 3,684 sq. ft.
- Elmwood School - 3,844 sq. ft.
- Crews on site for just 20 days
- Projects completed in 18 weeks

CONSTRUCTION

- Design-Build Format
- Two stories high
- Building Information Modeling (BIM)
- 95% of work completed off-site

DETAILS FOR EACH SCHOOL

- 5 Modules
- 25' x 28' classrooms
- 100 sq. ft. breakout room
- Four 14' x 60' modules stacked 2 over 2
- Single 14' x 60' stacked lengthwise to connect to existing school

FEATURES

- K-12 School Classroom Addition
- Architectural metal panel
- Mirrored the 25' x 28' dimensions of the existing classrooms
- Highly efficient electric heating/cooling rooftop units
- High-performance windows that matched the current school

Interior color scheme matched current schools.



We matched the exterior red brick and tan stucco finishes of the current schools.



Let's discuss your modular building options

Call 1-800-257-2536
triumphmodular.com

Triumph Modular | 194 Ayer Rd. Littleton, MA 01460



Redefining Modular™

Over 40 years of experience delivering award-winning, modern modular solutions.